

Field reference notes: DWR shift checklist

Start of shift

- Read the previous shift's logbook entries and open alarms.
- Check transmitter, antenna and servo status on the control screen.
- Confirm the latest volume scan reached the central server on time.
- Confirm the radar clock is synchronised.

During the shift

- Review reflectivity and velocity products after every volume.
- Treat sudden inbound/outbound pairs as possible aliasing until checked.
- Log every alarm with its start time, action taken, and whether it cleared.
- Switch to the severe-weather scan strategy when the SOP criteria are met.

Reflectivity guide

dBZ	Usual meaning
About 20	Light rain
40 and above	Moderate to heavy rain
50 and above	Very heavy rain, possible hail

Always check a strong ring of reflectivity against the melting level before treating it as heavy rain. It may be the bright band.

End of shift

- Write the handover: status, open alarms, weather situation, products issued, pending tasks.
- Walk the incoming officer through it and both sign the logbook.